



**SAMALESWARI REGIONAL CO-OPERATIVE MILK PRODUCERS' UNION LTD.**

**Regd. No.6/SM of 6<sup>th</sup> March 76**

**SAKHIPARA, SARLA CANAL ROAD, DHANKAUDA, DIST-SAMBALPUR (ODISHA) 768 006**

**Phone : (0663) 2548590, Fax : (0663) 2548520**

**E-mail : [omfedsrcmpul@gmail.com](mailto:omfedsrcmpul@gmail.com)/[omfedsrcmpul@rediffmail.com](mailto:omfedsrcmpul@rediffmail.com)/[omfedsrcmpul@yahoo.com](mailto:omfedsrcmpul@yahoo.com)**

Ref. No.: SRMU/

Dated:- 07.07.2017

**QUOTATION CALL NOTICE**

Sub : Quotation call Notice for **25 KVA 3 Phase Transformer, installation and commission.**

1. You are invited to submit your most competitive quotation for the following goods:-

Brief Description of the Goods	Quantity	Delivery Period	Place of Delivery	Installation Requirement if any
DP Mounted 11/0.4 KV- 25 KVA BEE star rated Sub-Station with 9 mtr. Long PSC Pole & Double Disc arrangement with suitable protective devices viz: A.B, Switch, H.G. Fuse, Lightening Arrester as per provision in the relevant I.E.Rule with 3 (Three) numbers earthing. The Transformer to be installed should have with LT bushing cover.	1 No.	Within 60 days from the date of issue of Supply Order	Milk Chilling Plant, Village Routbahal, (Dipupada) Dist.-Sambalpur	Yes
Cost of 11 KV 3 ph 3 wire line with 55 mm <sup>2</sup> AAAC and 9 meter long 300 Kg. PSC pole for pin point & 2 nos. cut point with double disc arrangement & 80 mtr. Span.	0.15 K.M	- Do -	- Do-	- Do-
Whole Current Meter	1 No.	- Do -	- Do-	- Do-
LTCT Meter with TP Box	1 No.	- Do -	- Do-	- Do-
3 & ½ Core 35 mm. 2 LT PVC Cable	30 Mtr.	- Do -	- Do-	- Do-
Inspection of Sub-station testing, commissioning of LTCT Meter and other work etc. including liasoning with WESCO and Electrical Inspector etc. and obtaining permission.				

- *Where ISI certification marked goods are available in market, purchase should generally be limited to goods with those or equivalent marking only.*
- *The offerer will tap from 11 KV Mahulpali feeder and draw 0.15 Km. 11 KV line 3 Ph. 3 wire with 55 mm<sup>2</sup> AAA Conductor at his own cost as per provision in the relevant I.E rule through a licensed electrical contractor. You will arrange right of way for erection of proposed 11 KV line. The XLPE cable will be maintained by the offerer at his own cost after effecting power supply to the point. A plan showing S/S, line to be approved before execution of work.*
- *Before commissioning of the line & Sub-station, it should be inspected by the Deputy Electrical Inspector, Rourkela proof of purchasing the required materials for the work have to be submitted to this office for verification prior to erection. The Transformer must be inspected at your cost by the WESCO authorities before installation of the same conforming to BIS specification. Other materials should also be inspected before use.*



**SAMALESWARI REGIONAL CO-OPERATIVE MILK PRODUCERS' UNION LTD.**

**Regd. No.6/SM of 6<sup>th</sup> March 76**

**SAKHIPARA, SARLA CANAL ROAD, DHANKAUDA, DIST-SAMBALPUR (ODISHA) 768 006**

**Phone : (0663) 2548590, Fax : (0663) 2548520**

**E-mail : [omfedsrcmpul@gmail.com](mailto:omfedsrcmpul@gmail.com)/[omfedsrcmpul@rediffmail.com](mailto:omfedsrcmpul@rediffmail.com)/[omfedsrcmpul@yahoo.com](mailto:omfedsrcmpul@yahoo.com)**

1. The Offerer should be a license Electrical Contractor from appropriate authority.
2. The Offerer will get the line and sub-station inspected by Dy.Electrical Inspector, Rourkela.
3. The Transformer must be inspected at Offerer's cost by the WESCO authorities before installation of the same confirming to 3 Star rated Transformer with BIS specification. Other materials should also be inspected before use.
4. From the Transformer up-to meter, LT cable is to be provided and one whole current meter of appropriate capacity shall be installed in suitable WESCO approved TP box to record the consumption at the entrance gate of the consumer's premises. The cost of which shall be deposited by you with the Executive Engineer, J.E.D, Jharsuguda under deposit work norm before execution of agreement.  
***All rules, regulations, norms & conditions of WESCO as approved by OERC Distribution (Condition of Supply) Code 2004 should be fulfilled before effecting power supply by the offerer.***
10. Interested Manufacturer/Supplier/Distributor may quote their rate indicating price, Tax,, Terms of Rate, Guarantee etc to the above address. **The detail technical specification, features of the Goods should be clearly mentioned in the quotation.** Boucher/Leaflet of the goods be attached with the quotation.
11. VAT Extra or CST 2% extra against form "C" for the taxable Item.
12. Quotation should remain valid for a period not less than **60 days** after the deadline date specified for submission.
13. Quotation should conform to the terms and conditions, and specifications.
14. Notwithstanding the above, the Purchaser reserves the right to accept or reject any quotations and to cancel the bidding process and reject any or all quotations at any time prior to the award of contract.
15. Payment shall be made within 30 days of installation and commission of all work and submission of all documents from WESCO and Electrical Inspector.
16. Normal commercial warranty/ guarantee shall be applicable to the supplied goods.
17. Term of supply i.e regarding Packing & forwarding, Insurance, Delivery Period and term of delivery should be clearly mentioned.
18. Quotation should reach latest by **15:00 hrs. on dt.25.07.2017** for our consideration.
19. All disputes are subject to Sambalpur jurisdiction.

**General Manager**